



**NOTES:**

- Remove existing centre line and Cycle lane lining from carriageway.
- Supply and install new centre line to diagram 1004. 4m White line with 2m gap. Centre line 100mm wide.
- Lining to be White Thermo Plastic Screed.
- Traffic sensitive area.
- Bus Route.

- Supply and install regulating layer of Mot Type 1 Sub base on existing carriageway/FW, 40mm Thick AC20 Binder Course with 30mm 15/10. HRA surface course with 8-14mm white chipping.
- High Friction Surfacing (Buff - 500mm strip) HAPAS Certification: Type 1, Epoxy based
- Plastic form/ pre-cast trapped gully with Class D400 grating and frame
- Supply and install new K1 concrete Kerb to be installed as per Fife Council Standard detail CS/SD11/01. New Kerb face 100mm.
- Supply and install new K3/1 kerbing as per Fife Council Standard details CS/SD11/03. K3/1 to be flush fitted to existing carriageway.
- Supply and install new K5 kerbing as per Fife Council Standard details CS/SD11/04.
- Supply and install new E1 edging kerb to Fife Council Standard detail.
- Supply and install new Castle Kerbing
- Raised Table



**HAZARDS AND RISKS WARNING**

The items listed below indicate known hazards or areas of significant risk.

- Item 1: High Voltage and Low Voltage Scottish power mains in carriageway, footways and verge with road crossings through out site, check public utilities.
- Item 2: SGN Medium Pressure main in southern verge, crosses over to northern verge just before Mount Frost Drive junction. Check public utilities.
- Item 3: Scottish Water, Scottish Power, British Telecom, GTC and Scotia Gas Network underground services in area. Public Utilities to be obtained before commencement of works, check public utilities
- Item 4: Bus Route with bus stops within works.
- Item 5: Pedestrian route.
- Item 6: Coal Tar Present

| REV   | AMENDMENTS | BY     | APPVD       | DATE          |
|---|------------|--------|-------------|---------------|
|   |            |        |             |               |
| <b>ASSETS, TRANSPORTATION &amp; ENVIRONMENT</b><br><small>HEAD OF SERVICE - Ken Gourlay</small> |            |        |             |               |
| TITLE: <b>B9130 Balbirnie Street Shared Footpath General Arrangement 1 of 3</b>                 |            |        |             |               |
| DRAFT   |            | TENDER |             | CONSTRUCTION  |
| DESIGNED  | MS/TM      | DRAWN  | MS/TM       | CHECKED       |
| DATE  | 07/01/2022 | SCALE  | N.T.S. @ A0 | DRAWING No. - |
|   |            |        | AS BUILT    |               |
|   |            |        | APPROVED    |               |